구 매 규 격 서

Commodity Description

종목 번호 Item No.	관세분류 번호 HSK No.	정부물품분류번호(8자리) Korean Government Commodity Classification Code(eight-digit)	품 명 Description	단 위 Unit	수 량 Q'ty
1	9030.39.9000	41113677	75kV 내전압시험기 (75kV Dielectric test set)	set	1

I. 용도(End-user's Use)

- 1. This equipment is used to perform AC dielectric testing for design evaluation, quality assurance and inspection of reliability and robustness on cables, switchgears, bushings, capacitors, fuses arrestors, motors etc.
- 2. This equipment shall be designed and build to comply with standards such as ISO/IEC, IEEE, JIS, DIN, EN, UL etc.

II. 장비의 구성(Configurations of Goods)

1. 본체(Main body) : 1 set

2. Accessories(부속장비)

Power and grounding cables1 set

Ⅲ. 성능 및 규격(Performance and Specification)

1. Power rating(1 hr ON / 1 hr OFF) : 75 kVA or more

2. Voltage rating : 75 kV or more

3. Accuracy of voltage : ±1 % or less

4. Output current at 75 kV(1 hr ON / 1 hr OFF) : 1 A or more

5. Accuracy of current : ±1 % or less

- 6. Partial Discharge at 75 kVA
- 7. Input power : 440 V, 60 Hz, 1Ø

: 2 pC or less

- 8. Control & Safety
 - ① Voltage meter
 - 2 Current meter
 - 3 Control power breaker
 - 4 Manual/auto output mode
 - 5 Test dwell timer(hour : min : sec)
 - 6 Ramp Rate control
 - ③ Switch(button) for emergency Off
 - ® Overload circuit adjustable from 10% to 110% of rated current

IV. 기타 조건(Remarks)

- 1. Two copy manuals in English or Korean for operation and maintenance
- 2. Installation and training
 - ① Location: 84, Yeonhwa-ri, Osan-myeon, Gokseong-gun, Jeollanam-do, Republic of Korea
 - ② Installation and training should be provided by contractor's qualified engineer at the customer site.
- 3. Contractor shall summit a KOLAS calibration report
- 4. Final Acceptance Test should be done by contractor at KTC's site.
- 5. One year warranty after the issue of KTC's final acceptance certificate
- 6. The bidder have to submit the published standard brochure(or catalogue) for reviewing the bid proposal.
- 7. 100% by irrevocable letter of credit at sight.(90% after shipping and 10% after inspection)